



LEVEL AND FLOOR CONTAINER NOTES	
Current Date:	10/9/2018
File Name:	Michael Hay Construction   Waterford Spec 3.mmd
Level Name:	Basement
Building Code - Design Methodology:	IRC2015
Floor Container:	FC1
Floor Area Loading is:	40 Live Load & 12 Dead Load
Maximum Allowed Deflection	L/480 Live Load & L/240 Total Load

Connector Summary									
Qty	Manuf	Product	Flange	Backer Blocks	Web Stiff	Skew	Slope	Supporting Mtl	Supported Mtl
6	Simpson	IUS 2.06/11.88	None	No	No	-	-	SCL	11 7/8" TJI® 210

Accessories				
PlotID	Length	Product	Plies	Net Qty
		3/4" Plywood or OSB (23/32" APA Rated Sheathing 48/24 Exposure 1)	1	64

Products				
PlotID	Length	Product	Plies	Net Qty
FJ1	36-00-00	11 7/8" TJI® 210	1	8
FJ2	32-00-00	11 7/8" TJI® 210	1	2
FJ3	30-00-00	11 7/8" TJI® 210	1	25
FJ4	26-00-00	11 7/8" TJI® 210	1	6
FJ5	20-00-00	11 7/8" TJI® 210	1	3
FJ6	18-00-00	11 7/8" TJI® 210	1	2
FJ7	12-00-00	11 7/8" TJI® 210	1	1
FJ8	8-00-00	11 7/8" TJI® 210	1	1
FJ9	6-00-00	11 7/8" TJI® 210	1	2
FJ10	4-00-00	11 7/8" TJI® 210	1	3
FJ11	2-00-00	11 7/8" TJI® 210	1	2
BM1	6-00-00	1 3/4" x 11 7/8" 1.9E Microllam® LVL	1	1
BM2	4-00-00	1 3/4" x 11 7/8" 1.9E Microllam® LVL	2	2
BM3	16-00-00	1 3/4" x 14" 2.0E Microllam® LVL	3	3
Ca1	16-00-00	1 1/4" x 11 7/8" 1.3E TimberStrand® LSL	1	15
Bk1	21-00-00	11 7/8" TJI® 210	1	1
Pt1	10-00-00	4x4 DF No.2	1	1



Idaho Falls, LBM

DESIGNER: Robert Billman

PHONE: 208-557-5053

E-MAIL: Bob.Billman@Buildwithbmc.com

Job Number: XXX

Date: 10/09/2018

Builder: Michael Hay Construction

Job Name: Waterford Pec 3

Address: XXX

City, St.: XXX