



Products				
PlotID	Length	Product	Plies	Net Qty
FJ1	36' 0"	11 7/8" TJI® 110	1	11
FJ2	28' 0"	11 7/8" TJI® 110	1	5
FJ3	26' 0"	11 7/8" TJI® 110	1	25
FJ4	18' 0"	11 7/8" TJI® 110	1	9
FJ5	10' 0"	11 7/8" TJI® 110	1	2
BM1	6' 0"	1 3/4" x 11 7/8" 2.0E Microllam® LVL	1	1
Ca1	16' 0"	1 1/4" x 11 7/8" 1.3E TimberStrand® LSL	1	13

Wall Framing				
PlotID	Length	Product	Plies	Net Qty
Hd1	6' 0"	2x10 DF No.2	2	2
Hd2	4' 0"	2x10 DF No.2	2	8
Hd3	6' 0"	2x4 DF No.2	1	7
Hd4	4' 0"	2x4 DF No.2	1	5

Accessories				
PlotID	Length	Product	Plies	Net Qty
		3/4" Plywood or OSB (23/32" APA Rated Sheathing 48/24 Exposure 1)	1	61

Connector Summary									
Qty	Manuf	Product	Flange	Backer Blocks	Web Stiff	Skew	Slope	Supporting Mtl	Supported Mtl
4	Simpson	IUS 1.81/11.88	None	No	No	-	-	SCL	11 7/8" TJI® 110

LEVEL AND FLOOR CONTAINER NOTES	
Current Date:	3/7/2019
File Name:	bo-Greg Armstrong - Frye.mmdl
Level Name:	Basement
Building Code - Design Methodology:	IRC2015
Floor Container:	FC1
Floor Area Loading is:	40 Live Load & 12 Dead Load
Maximum Allowed Deflection	L/480 Live Load & L/240 Total Load

Idaho Falls, LBM

DESIGNER: Blaine Eborn

PHONE: 208-557-5056

E-MAIL: Blaine.Eborn@BuildWithBMC.com

Job Number: XXX

Date: 3/7/19

Builder: Greg Armstrong

Job Name: Frye Residence

Address: XXX

City, St.: Bonneville County, ID

