



Products				
PlotID	Length	Product	Plies	Net Qty
FJ1	16' 0"	11 7/8" TJI@ 110	1	14
Ca1	16' 0"	1 1/4" x 11 7/8" 1.3E TimberStrand® LSL	1	4
LG1	20' 0"	1 3/4" x 11 7/8" 2.0E Microllam® LVL	1	1

Accessories				
PlotID	Length	Product	Plies	Net Qty
		3/4" Plywood or OSB (23/32" APA Rated Sheathing 48/24 Exposure 1)	1	11

Connector Summary									
Qty	Manuf	Product	Flange	Backer Blocks	Web Stiff	Skew	Slope	Supporting Mtl	Supported Mtl
14	Simpson	IUS 1.81/11.88	None	No	No	-	-	SCL	11 7/8" TJI@ 110

LEVEL AND FLOOR CONTAINER NOTES	
Current Date:	10/28/2019
File Name:	jf-Windriver - Hix Addition.mmdl
Level Name:	Basement
Building Code - Design Methodology:	IRC2015
Floor Container:	FC1
Floor Area Loading is:	40 Live Load & 12 Dead Load
Maximum Allowed Deflection	L/480 Live Load & L/240 Total Load



Idaho Falls, LBM
 DESIGNER: Blaine Eborn
 PHONE: 208-557-5056
 E-MAIL: Blaine.Eborn@BuildWithBMC.com

Builder: Windriver Homes
 Job Name: Hix Addition
 Address: XXX
 City, St.: XXX

Job Number: XXX
 Date: 10/28/19